BRUHAT BANGALORE MAHANAGARA PALIKE

Modified Schedule -B

Package-1, includes 10works of Rs. 80.00 lakhs

Sl No	Modified Quantity	Description	Unit	Approved Tender Rates of GOPIREDDY ( )		
				In Figures		In Words
1	5.40	KSRB 2-1.1: Earth work in surface excavation in ordinary soil for leveling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe line and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed as per specifications, Specification No KBS 2.1(a) / 2.3.1,P. No. 5/ Item No. 2.1/ PWD SR 2016-17	Cum	158.0	853.2	Rupees One Hundred Fifty Eight Only
2	76.54	KSRB 2-2.1 : earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in Ordinary soil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications, specification, No, KBS 2.1(a) / 2.3.5, No. 5/ Item No. 2.3/ PWD SR 2016-17(Quantity upto 125%)	Cum	191.0	14618.7	Rupees One Hundred Ninety One Only
	144.59	Quantity Above 125%	Cum	302.38	43722.2	Rupees Three Hundred Two and Thirty Eight Paise
3	2.61	KSRB-4-1.3 : Providing and laying in position plain cement concrete of mix M 7.5 with OPC cement at 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2, No. 12/ Item No. 4.3/ PWD SR 2016-17 With Area Weightage @ 8% (Quantity upto 125%)	cum	4922.0	12858.7	Rupees Four Thousand Nine Hundred Twenty Two Only
	56.36	Quantity above 125%	cum	5159.7	290801.5	Rupees Five Thousand One Hundred Fifty Nine
4	58.00	providing & laying plain cc of mix m20 With Area Weightage @ 6%	cum	5064.0	293712.0	Rupees Five Thousand Sixty Four Only
5	31.60	KSRB 5.2-2 Providing and constructing granite / trap / basalt rubble stone masonry in foundation with mud mortar 1:8, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5.1.13 Page No. 25/ Item No. 5.5/ PWD SR 2016-17(Quantity upto 125%)	cum	4082.0	128991.2	Rupees Four Thousand Eighty Two Only
	39.14	Quantity above 125%	Cum	4544.8	177884.9	Rupees Four Thousand Five Hundred Forty Four

Gopi Reddy

Signature of the Contractor

Executive Engineer

Scanned by CamScanner

Sl No	Modified Quantity	Description	Unit	Approved Tender Rates of GOPIREDDY ( )		
				In Figures		In Words
6	0	KSRB 5.3-1 Providing and constructing granite / trap / basalt size stone masonry in basement with mud mortar, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5-1.13 Page No. 23/ Item No. 5.9/ PWD SR 2016-17	Cum	5062.0	0.0	Rupees Five Thousand Sixty Two Only
7	6.31	KSRB 4.2.2 : Providing and laying in position Reinforced cement concrete of mix M20 withOPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum with superplastesisre @ 3lts conforming to IS9103-1999Reffirmed machine mixed exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, walls(any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour HOM of machinery, curing, complete as per specifications. Specification. No. KBS 4.1,4.6, No. KBS 4.1,4.6, No. 13/ Item No. 4.11/ PWD SR 2016-17(Quantity upto 125%)	Cum	6079.0	38373.7	Rupees Six Thousand Seventy Nine Only
	6.76	(Quantity above 125%)	Cum	5723.0	38684.0	Rupees Five Thousand Seven Hundred Twenty Three and One Paise Only
8	0.48	KSRB 4.9.2:providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications.Specification No. KBS 4.6.3 Page No. 17/ Item No. 4.46/ PWD SR 2016-17(Quantity upto 125%)	tonne	61292.0	29113.7	Rupees Sixty One Thousand Two Hundred Ninety Two Only
	1.20	(Quantity above 125%)	tonne	78889.4	95044.0	Rupees Seventy Eight Thousand Eight Hundred Eighty Nine and Forty One Paise Only
9	0.00	KSRB 5-14 : Providing and constructing precast concrete solid blocks with compressive strength not les than 35 Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x20x20 cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. Page No. 24/ Item No. 5.27/ PWD SR 2016-17	Sqm	948.0	0.0	Rupees Nine Hundred Forty Eight Only
10	0.00	Providing flush pointing to square rubble, course or uncoursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. Page No. 119/ Item No. 15.1 PWD SR 2016-17	sqm	98.0	0.0	Rupees Ninety Eight Only

Signature of the Contractor

Executive Engineer

Scanned by CamScanner

Sl No	Modified Quantity	Description	Unit	Approved Tender Rates of GOPIREDDY ( )		
				In Figures		In Words
6	0	KSRB 5.3-1 Providing and constructing granite / trap / basalt size stone masonry in basement with mud mortar, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5-1.13 Page No. 23/ Item No. 5.9/ PWD SR 2016-17	Cum	5062.0	0.0	Rupees Five Thousand Sixty Two Only
7	6.31	KSRB 4.2.2 : Providing and laying in position Reinforced cement concrete of mix M20 withOPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum with superplastesisre @ 3lts conforming to IS9103-1999Reffirmed machine mixed exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, walls(any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour HOM of machinery, curing, complete as per specifications. Specification. No. KBS 4.1,4.6, No. KBS 4.1,4.6, No. 13/ Item No. 4.11/ PWD SR 2016-17(Quantity upto 125%)	Cum	6079.0	38373.7	Rupees Six Thousand Seventy Nine Only
	6.76	(Quantity above 125%)	Cum	5723.0	38684.0	Rupees Five Thousand Seven Hundred Twenty
8	0.48	KSRB 4.9.2:providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications.Specification No. KBS 4.6.3 Page No. 17/ Item No. 4.46/ PWD SR 2016-17(Quantity upto 125%)	tonne	61292.0	29113.7	Rupees Sixty One Thousand Two Hundred Ninety Two Only
	1.42	(Quantity above 125%)	tonne	78889.4	112178.8	Rupees Seventy Eight Thousand Eight Hundred
9	0.00	KSRB 5-14 : Providing and constructing precast concrete solid blocks with compressive strength not les than 35 Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x20x20 cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. Page No. 24/ Item No. 5.27/ PWD SR 2016-17	Sqm	948.0	0.0	Rupees Nine Hundred Forty Eight Only
10	0.00	Providing flush pointing to square rubble, course or uncoursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. Page No. 119/ Item No. 15.1 PWD SR 2016-17	sqm	98.0	0.0	Rupees Ninety Eight Only

Gopi Reddy
Signature of the Contractor

Executive Engineer

Scanned by CamScanner

l No	Modified Quantity	Description	Unit	Approved Tender Rates of GOPIREDDY ( ) In Figures		In Words
11	0.00	"SOLID PVC DOOR FRAMEProviding & fixing factory made PVC Door frame of size 50x47 mm with a wall thickness of 5mm, made out of extruded 5mm rigid PVC foam sheet metered cut at corners & jointed 2No.s of 150mm long brackets of 15x15 mm M.S. Square tube of 19 gauge. The door frame to be fixed to the wall using M.S. Screws of 65/80mm size complete as per manufactures specification & direction of Engineer-in charge Page No. 57/ Item No. 9.84/ PWD SR 2016-17	Sqm	532.0	0.0	Rupees Five Hundred Thirty Two Only
12	0.00	SOLID PANEL PRELAM PVC DOOR SHUTTERProviding & fixing 30mm thick factory made rigid foam prelam panelled Door Shutters made from M.S. tube of 19x19mm, 19 gauge for styles and 15x15mm for top & bottom rails, covered with heat moulded prelaminated PVC 'C' Channel of 5mm thick sheet & 30x50mm wide of form styles & 5mm thick & 75mm wide prelaminated PVC sheets for top rail, lock rail & bottom rail on either side & 5mm thick, 20mm wide cross PVC sheet as gap insert for top rail & bottom rail, Panelling of 5mm thick PVC sheet Prelaminated on either side fitted in the M.S. frame, sealed to the styles &rails with PVC designer beading on either side & joined together with solvent cement adhesive etc., complete as per manufactures specification & direction of Engineer –in-charge fixed to frames with 3nos of 75mm. Aluminium hinges. With Both Side Prelam Page No. 58/ Item No. 9.85/ PWD SR 2016-17	0.00	4090.0	0.0	Rupees Four Thousand Ninety Only
13	370.03	KSRB 15.3.13 : Providing 12mm thick cement plaster in single coat with cement mortar 1:3, to ceiling including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications Page No. 110/ Item No. 15.21 PWD SR 2016-17	Sqm	195.0	72154.9	Rupees One Hundred Ninety Five Only
14	69.25	KSRB 15-3.7:- Providing 18mm thick cement plaster in single coat with cement mortar 1:3, to brick masonry including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. Page No. 109/ Item No. 15.15/ PWD SR 2016-17(Quantity upto 125%)	Sqm	247.0	17104.8	Rupees Two Hundred Forty Seven Only
	296.15	Quantity above 125%	Sqm	279.1	82662.0	Rupees Two Hundred Seventy Nine and Twelve
15	0.00	KSRB 15.3.10 : Providing 20mm thick cement plaster in single coat with cement mortar 1:4, to stone masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. Page No. 110/ Item No. 15.18 / PWD SR 2016-17	Sqm	223.0	0.0	Rupees Two Hundred Twenty Three Only

Gopi Reddy
Signature of the Contractor

Executive Engineer

Scanned by CamScanner

Sl No	Modified Quantity	Description	Unit	Approved Tender Rates of GOPIREDDY ( )		
				In Figures		In Words
16	0.00	KSRB 15.4.1 : Extra for providing and mixing water proofing compound in cement plaster work at one kg per bag or in the proportion recommended by the manufactures, for cement mortar 1:3, 12mm thick cost of materials complete as per specifications. Page No. 110/ Item No. 15.23/ PWD SR 2016-17	Sqm	7.0	0.0	Rupees Seven Only
17	4.88	KSRB 4-6.2 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness upto 200 mm including cost of all materials, labour complete as per specifications. Specification NO KBS 4.6.2 Page No. 15/ Item No. 4.29.2/ PWD SR 2016-17	Sqm	556.0	2710.5	Rupees Five Hundred Fifty Six Only
18	0.00	KSRB 15.7: Providing lime rendering for plastering to wall and ceiling, including cost of materials, labour, curing complete as per specifications. Page No. 110/ Item No. 15.17/ PWD SR 2016-17	Sqm	200.0	0.0	Rupees Two Hundred Only
19	0.00	KSRB 15-3.7:- Providing 18mm thick cement plaster in single coat with cement mortar 1:3, to brick masonry including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. Page No. 109/ Item No. 15.15/ PWD SR 2016-17	Sqm	247.0	0.0	Rupees Two Hundred Forty Seven Only
20	92.18	KSRB 15.15.3: Providing and applying painting in one coat with plastic emulsion paint of approved brand and manufacture on wall surface to give an even approved shade after thoroughly brushing the surface free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth cost of materials, labour, complete as per specifications. Page No.114/ Item No. 15.52 / PWD SR 2016-17(Quantity upto 125%)	Sqm	45.0	4147.9	Rupees Forty Five Only
	398.19	(Quantity above 125%)	Sqm	56.63	22550.7	Rupees Fifty Six and Sixty Three Paise Only
21	0.00	Providing and fixing Ceramic tiles of size 400x400mm for flooring, threads,steps and landing,laid on a bed of 20mm thick cement morta. 1:3 mix flush pointing with white cement mixed with matching colour pigment including curing, clearing etc. complete .The Worked including curing., clearing etc., complete, The work includes cost of all materials. Labour charges for all items or work, hire charges for equipment, etc., complete as per specification. Page No. 116/ Item No. 14.63 / PWD SR 2016-17	Sqm	1087.0	0.0	Rupees One Thousand Eighty Seven Only
22	0.00	KSRB 14.17.2: Providing skirting, dado, rises of steps with Colour glazed tiles 6mm thick on 10mm thick cement plaster 1:3 and jointed with white cement slurry over rough plaster surface (excluding cost of rough plastered surface white should be measured and paid separately) using glazed tiles of approved make and size of materials, labour, complete as per specifications. Specification No. KBS 14.17. Page No. 103/ Item No. 14.41.1 / PWD SR 2016-17	Sqm	1084.0	0.0	Rupees One Thousand Eighty Four Only

Signature of the Contractor

Executive Engineer

Scanned by CamScanner

Sl No	Modified Quantity	Description	Unit	Approved Tender Rates of GOPIREDDY ( )		
				In Figures		In Words
23	808.42	SKSRB 15-16 : Providing and finishing external walls in two coats with waterproof cement paint of approved brand and shade to given an even shade after thoroughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications. Page No. 114/ Item No. 15.53.2 / PWD SR 2016-17	Sqm	85.0	68715.5	Rupees Eighty Five Only
24	0.00	KSRB 15.17.8 : Extra over item No. 15-17.6 for applying every subsequent coat of enamel paint to give an even shade after cleaning the surface of all dirt, dust and foreign matter, sand papering including cost of materials, labour, complete as per specifications. Page No.113/ Item No. 15.60.2 / PWD SR 20114-15	Sqm	49.0	0.0	Rupees Forty Nine Only
25	0.00	Providing and fixing chlorinated poly veny chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing, this including jointing of pipes and fittings with one step CPVC solvent cement and the cost of cutting chases & making good the same including testing of joints complete.(concealed work including cutting chases and good the walls etc,),15mm nominal OD pipes Page No. 92/ Item No. 13.83.1/ PWD SR 2016-17	m	253.0	0.0	Rupees Two Hundred Fifty Three Only
26	0.00	KSRB 13-6.1.2 : Providing and fixing in position brass bib cock of approved quality 20mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification NO. KBS 13.2.2 / 13.3, Page No. 88/ Item No. 13.24 / PWD SR 2016-17	Each	246.0	0.0	Rupees Two Hundred Forty Six Only
27	0.00	KSRB 11-2 : Providing and fixing white vitreous china clay, water closets Orissa pattern of size 580 x 440mm with integral type footrests, 100m S or P trap, 10 litre low level, P. V. C. flushing cistern (all are approved make) with fittings, C.I. / M.S. brackets, 32mm diameter flush pipe fittings and clamps, overflow arrangements with specials and 25mm mosquito proof coupling of approved design, painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications.Specification No. KBS Page No. 78/ Item No. 12.2 PWD SR 2016-17	Unit	4304.0	0.0	Rupees Four Thousand Three Hundred Four Only
28	0.00	Providing and fixing CI Nahani Trap of approved make conforming to ISI specifications and construction of cistern in CC 1:2:4 as per directions (Rate is inclusive of cost of materials and fixtures and conveyance of materials to work spot).10 cms x 7.5cms, Page No.91/ Item No. 12.113.1 PWD SR 2016-17	Each	248.0	0.0	Rupees Two Hundred Forty Eight Only
29	0.00	KSRB 13-6.1.2 : Providing and fixing in position brass bib cock of approved quality 20mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification NO. KBS 13.2.2 / 13.3, Page No. 88/ Item No. 13.24 / PWD SR 2016-17	Each	246.0	0.0	Rupees Two Hundred Forty Six Only

Gopireddy
Signature of the Contractor

Executive Engineer

Scanned by CamScanner

Sl No	Modified Quantity	Description	Unit	Approved Tender Rates of GOPIREDDY ( )		
				In Figures		In Words
30	0.00	KSRB 11.11.3 : Providing and fixing white vitreous china clay, flat back wash basin of size 550x400mm with pair of 15mm C.P brass pillar taps with C.I./M.S. brackets, 32mm C.P. brass waste of standard pattern, painting of fitting and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications. Specification No. KBS 11. Page No.82/ Item No. 12.25 PWD SR 2011-12	Unit	3597.0	0.0	Rupees Three Thousand Five Hundred Ninety Seven Only
31	0.00	KSRRB 300-1. Earth work excavation by manual means in Ordinary Soil soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications.MORTH chapter 3. No. 141/ Item No. 19.1/ PWD SR 2016-17	Cum	83.0	0.0	Rupees Eighty Three Only
32	35.87	KSRB-4-1.3 : Providing and laying in position plain cement concrete of mix M 1:4:8 withOPC cement at 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2, No. 12/ Item No. 4.3/ PWD SR 2016-17	Cum	4922.0	176552.1	Rupees Four Thousand Nine Hundred Twenty Two Only
33	0.00	KSRB 5.2.3 Providing and constructing granite / trap / basalt Size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5.1.13 Page No. 23/ Item No. 5.6/ PWD SR 2016-17	cum	4234.0	0.0	Rupees Four Thousand Two Hundred Thirty Four Only
34	0.00	KSRB 4-1.7 : : Providing and laying in position plain cement concrete of mix 1:3:6 withOPC cement @ 220kgs, with 20mm and down size graded granite metal coarse aggregates @0.84cum and fine aggregates @0.56cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2/P No. 13/ Item No. 4.7/ PWD SR 2016-17 With Area Weightage @ 8%	cum	5342.0	0.0	Rupees Five Thousand Three Hundred Forty Two Only
35	8.26	Compound Wall & Coping concrete CC 1:3:6 With Area Weightage @ 6%	cum	5270.0	43540.7	Rupees Five Thousand Two Hundred Seventy

Gopireddy
Signature of the Contractor

Executive Engineer

Scanned by CamScanner

Sl No	Modified Quantity	Description	Unit	Approved Tender Rates of GOPIREDDY ( )		
				In Figures		In Words
36	0.00	Supplying and fixing M.S rectangular poles made out of 2 equal angles of 65x656 mm welded together and fixed in CC (1:2:4) with 2 NOS 16 mm dia, M.S hold fast rods each of length 25 cms, including cost of all materials cutting, bending scaffolding wherever necessary, nicely finishing the welded joints with all lead lifts and as per the directions of the Engineer in charge of the work and including providing 2 coats of approved quality paint over one coat of shop painting (excluding cost of earthwork and concrete), No.265/ Item No. 37.2 PWD SR 2016-17	m	828.0	0.0	Rupees Eight Hundred Twenty Eight Only
37	0.00	Providing and fixing M.S. Block pipe of 38 mm dia, of heavy guage of 14 including removing the bends, cutting the pipe, and fixing pipe in between the two vertical poles (M.S rectangular poles) and spot welding the chain link with M.S. block pipe including cost of all materials wastage in cutting, and scaffolding wherever necessary with all lead and lift as directed by the engineer in charge of work etc, complete including two coats of approved quality paint over one coat of shop paint, No. 265 Item No. 37.4 PWD SR 2016-17	m	328.0	0.0	Rupees Three Hundred Twenty Eight Only
38	0.00	Providing chain link fencing 50 mm size of 8 guage properly stretched between rectangular poles and fixed with suitable bolts & nuts, the free ends shall bed welded to the pole and block pipe at top and bottom as required including cost of all materials, labour, lead and lifts and as per the directions of the engineer – in charge of work including two coats of approved quality paint over one coat of shop paint, No. 265/ Item No. 37.3 PWD SR 2016-17	Sqm	666.0	0.0	Rupees Six Hundred Sixty Six Only
39	0.00	KSRB 15-18.2 : Providing and applying enamel metal paint two coats (excluding priming coat) over new steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications. Page No. 104/ Item No. 15.74/ PWD SR -2016-17	Sqm	83.0	0.0	Rupees Eighty Three Only
40	298.10	KSRRB 300-1. Earth work excavation by manual means in Ordinary Soil soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications.MORTH chapter 3. No. 143/ Item No. 19.1/ PWD SR 2018-19	Cum	129.0	38454.9	Rupees One Hundred Twenty Nine Only
41	428.34	KSRB 4-6.7 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for sides and soffits of beams, beam haunchings, cantilever girders, bressumers and lintels not exceeding 1 m in depth including cost of all materials, labour complete as per specifications. Specification NO KBS 4.6.2 Page No. 17/ Item No. 4.34/ PWD SR 2018-19(Quantity upto125%)	Sqm	290.0	124218.6	Rupees Two Hundred Ninety Only

Signature of the Contractor

Executive Engineer

Scanned by CamScanner

Sl No	Modified Quantity	Description	Unit	Approved Tender Rates of GOPIREDDY ( )		
				In Figures		In Words
42	59.56	KSRB 4.2.2 : Providing and laying in position plain cement concrete of mix M20 withOPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum with superplastesisre @ 3lts conforming to IS9103-1999Reffirmed machine mixed exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, walls(any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour HOM of machinery, curing, complete as per specifications. Specification. No. KBS 4.1,4.6, No. KBS 4.1,4.6, No. 14/ Item No. 4.11/ PWD SR 2018-19	Cum	5617.0	334548.5	Rupees Five Thousand Six Hundred Seventeen Only
43	5.14	KSRB 4.9.2:providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete	Qntl	70440.0	362061.6	Rupees Seventy Thousand Four Hundred Forty Only
44	124.38	Precast slab 20mm and down size for slab (including steel reinforcement) including centring and shutterng machine mixed concrete laid in layers not exceeding 15cms thick well compacted cost of all materials labour HOM of machineries curing complete as per specifications c.c 1:1.5:3 Including all cost of Matirial (DATA RATE ENCLOSED) 10cm thick RCC pre cast slab	Sqm	1739.0	216296.8	Rupees One Thousand Seven Hundred Thirty Nine Only
45	165.65	KSRRB M100-2. Loading and Unloading of stone boulders by manual means complete as per specification MORTH-100/chapter-1 Page No. 136/ Item No. 17.1/ PWD SR 2018-19	Cum	56.0	9276.4	Rupees Fifty Six Only
46	0.00	KSRB 2-1.1: Earth work in surface excavation in ordinary soil for leveling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe line and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed as per specifications, Specification No KBS 2-1.1, pg No. 6/ Item No. 2.1/ PWD SR 2018-19	cum	247.0	0.0	Rupees Two Hundred Forty Seven Only
47	125.55	KSRRB M100-1 Loading and unloading of stone boulder/stone aggregates/ sand/ kanker/ moorum. KSRRB M100-1:Placing tipper at loading point loading with front end loading, dumping turning for return trip, excluding time for haulage and return trip complete as per specification MORTH Chapter 1 (Page 136, item No. 17.1)	cum	88.0	11048.4	Rupees Eighty Eight Only
48	300.00	KSRB- 15-18.2 : Providing and applying enamel metal paint two coats (excluding priming coat) over new steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications. (Item No. 15.74, P. 123/ PWD SR 2018-19)	sqm	94.0	28200.0	Rupees Ninety Four Only

Signature of the Contractor

Executive Engineer

Scanned by CamScanner

Sl No	Modified Quantity	Description	Unit	Approved Tender Rates of GOPIREDDY ( )		
				In Figures		In Words
49	0.00	KSRB 4-1.3 : Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220 kgs with 40mm and down size graded granite metal coarse aggregates @ 0.892cum and fine aggregares @ 0.465 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2. pg No. 13/ Item No. 4.2/ PWD SR 18-19	cum	5155.0	0.0	Rupees Five Thousand One Hundred Fifty Five Only
50	4.50	KSRB- 4-1.5 : Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 300 kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregares @ 0.43 cum with superplastisiser @ 3lts confirming to IS9103-1999 reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications, specification. No. KBS 4.1,4.2,pg No. 13/ Item No. 4.5(Quantity upto125%)	Cum	5288.0	23796.0	Rupees Five Thousand Two Hundred Eighty Eight Only
	16.80	(Quantity above125%)	Cum	5388.3	90543.1	Rupees Five Thousand Three Hundred Eighty
51	176.40	Supplying and fixing MS rectangular poles made out of 2 equal angles of 65x65x6 mm welded together and fixed in CC 1:2:4 with 2 No. of 16mm dia MS hold fast rods each of length 25 cm, including ocst of all materials, cutting, bending, scaffolding wherever necessary, nicely finishing the welded joints with all leads and lifts and as per the directions of the Engineer in charge of the work and including providing 2 coats of approved quality paint over one coat of shop painting (excluding cost of earthwork and concrete) (P. 262, I. 37.2)	m	853.0	150469.2	Rupees Eight Hundred Fifty Three Only
52	98.00	Providing and fixing MS block pipe of 38 mm dia of heavy guage of 14 including removing the bends, cutting the pipe, and fixing pipe in between the existing two verticle poles (MS rectangular poles) and spot welding the chain link with MS block pipe including cost of all materials, wastage in cutting and scaffolding whereever necesssary with all lead and lift as directed by the Engineer in charge of the work and including providing 2 coats of approved quality paint over	M	405.0	39690.0	Rupees Four Hundred Five Only
53	225.00	Providing chainlink fencking 50mm size of 8 guage properly stretched between existing rectangular poles andfixed with suitable bolts and nuts, the free ends shall be welded to the pole and block pipe at top and bottom as required including cost of all materials, labour, lead and lifts as per the direcdtions of the Engineer in charge of the work and including providing 2 coats of approved quality paint over one coat of shop paint (PWDSR 2015-16, P. 266, I. 37.3)	cum	710.0	159750.0	Rupees Seven Hundred Ten Only

Signature of the Contractor

Executive Engineer

Scanned by CamScanner

Sl No	Modified Quantity	Description	Unit	Approved Tender Rates of GOPIREDDY ( )		
				In Figures		In Words
54	0.00	KSRB4-1.6: Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240 kgs, with 20 mm and down size graded granite matel coarse aggregates @ 0.878 cum and fine aggragtes @ 0.53cum, machine mixed concrete laid in layers not eceeding 15 cms, thick well compacted, in foundation, plinth and cills including cost of all materials, labour HOM machinery curing complate as per	Cum	5382.0	0.0	Rupees Five Thousand Three Hundred Eighty Two Only
55	29.75	KSRB 5.3-1:Providing and constructing granite /trap/basalt size stone masonry in foundation with cement mortar 1:6, stone hammered dressed in courses not less than 20cms hign, bond stones at two m apart in each course including cost of materials, labour, curing etc., complete as per specifications.(P-25. Item No. 5.6) Quantity upto 125%)	Cum	4562.0	135737.7	Rupees Four Thousand Five Hundred Sixty Two Only
56	64.80	KSRB 15.1.4: Providing ruled pointing to coursed stone masonry with cement mortar 1:4, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications cement mortar 1:4. Page No. 115 / Item No. 15.4 / PWD SR 2018-19	Sqm	139.0	9007.2	Rupees One Hundred Thirty Nine Only
57	81.00	Providing and fixing 20 cm thick pre cast RCC covering slab using reinforced cement concrete M 20 mix with stone aggregate 20 mm and down size including centring shuttering reinforcement and bar bending machine mixed concrete laid in layers not exceeding 15 cm thick wellcompacted cost of all materials labour curing comlete as per specification (Data Rate)	Sqm	4786.0	387666.0	Rupees Four Thousand Seven Hundred Eighty Six Only
58	1040.00	Providing and fixing Pre cast solid concrete kerb stones made out of CC 1:2:4 of size 450x150x500 mm and finished with CM 1:3 plastering and finishing cutting etc., complete.Pg No. 27, Item No.5.29.1	Sqm	439.0	456560.0	Rupees Four Hundred Thirty Nine Only
59	468.00	KSRB 5-9.1:Providing and applying ready mix priming coat over oncrete / masonry, / asbestos cement sheet / plastered surfaces includding preparing the surface after thorougly cleaning of oil, grease, dirt and other foreign matter and sand papering including cost of materials, labour compelte as per specifications. Page No. 124 / Item No. 15.80	Sqm	36.0	16848.0	Rupees Thirty Six Only
60	0.00	Providing and removing Centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square / rectangular slabs /side walls polygon in plan including cost of materials, labour complete as per specification and directions of the Engineer in charge.(Page No.16, Item NO.4.32)	Sqm	452.0	0.0	Rupees Four Hundred Fifty Two Only
61	0.00	Providing and placing on terrace, polyethylene water storage tanks asper IS 12707:1996 with manhole lid and suitable locking arrangements, making holes of suitable diameter for inlet, outlet and over flow pipes, including cost of materials, labour, transport charges, HOM and testing complete as per specifications for 1000 litre capacity.(Page No.96, Item NO.3.78)	Nos	6777.0	0.0	Rupees Six Thousand Seven Hundred Seventy Seven Only

Signature of the Contractor

Executive Engineer

Scanned by CamScanner

Sl No	Modified Quantity	Description	Unit	Approved Tender Rates of GOPIREDDY ( )		
				In Figures		In Words
62	288.00	KSRB 15-16.1 : Providing and finishing external walls in two coats with waterproof cement paint of approved brand and shade to give an even shade after throughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications.	Sqm	70.0	20160.0	Rupees Seventy Only
63	269.50	KSRB 14.6-1: Providing and laying heavy duty cobble stones 60mm thick interlock pavers, using cement and course sand for manufacture of blocks of approved size, shape and colour with a minimum compressive strength of 281 kg per sqm over 50mm thick sand bed (average thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in between joints, final compaction of paver surface joints into its final level, including cost of materials, labour and HOM of machineries complete as per specifications. Specification No. KBS. (P.No. 103, I.No. 14.6 of CSR 2016-17)	Sqm	1065.0	287017.5	Rupees One Thousand Sixty Five Only
64	12.30	KSRRB M100-1 Loading and unloading of stone boulder/stone aggregates/ sand/ kanker/ moorum. KSRRB M100-1:Placing tipper at loading point loading with front end loading, dumping turning for return trip, excluding time for haulage and return trip complete as per specification MORTH Chapter 1 (Page 118, item No. 17.1)	Cum	88.0	1082.4	Rupees Eighty Eight Only
65	0.00	KSRB 2-2.2 : Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications. specification. No. KBS 2.1(b) / 2.3.5.	Cum	286.0	0.0	Rupees Two Hundred Eighty Six Only
66	4.32	KSRB 7.9 : Providing and fixing M.S.grill work for windows and ventilators weighing 21kg/sqm using M.S. flats, or M.S. square rods, or combination of M.S. flats and square rods as per approved design, drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer, cost of materials, fixtures, labour and HOM of machinery complete as per specifications. Specification No. KBS 7.12.	Kg	79.0	341.3	Rupees Seventy Nine Only
67	12.60	PVC DOOR Shutter : Supply and fixing of doors shuttersmade of rigid PVC extruded hollow section of 20mm X 200mm with the wall thickness of 1.0mm + /0.1mm equally divided into 4nos with tongue and groove locking arrangements. The shutter frame is made of 58*24 mm with the wall thickness of 1.5mm+/-0.15mm section metricut and joined at 4 corners with 125mmX225mm plastic brackets. The shitter shall be horizontally reinforced with 2nos of 8mm PVC rods. Teak wood battons shall be reinforced inside the door shutter during the fabrication of the door shutter at those points wherever the hardware is fixed on to the door shutter.	Sqm	1779.0	22415.4	Rupees One Thousand Seven Hundred Seventy Nine Only

Signature of the Contractor

Executive Engineer

Scanned by CamScanner

Sl No	Modified Quantity	Description	Unit	Approved Tender Rates of GOPIREDDY ( )		
				In Figures		In Words
68	115.2	KSRB15-3.10 : Providing 20mm thick cement plaster in single coat with cement mortar 1:3, to stone masonry & concrete surface including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.	Sqm	262.0	30182.4	Rupees Two Hundred Sixty Two Only
69	46.92	KSRB 15-16.1 : Providing and finishing external walls in two coats with waterproof cement paint of approved brand and shade to give an even shade after throughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications.	Sqm	41.0	1923.7	Rupees Forty One Only
70	141.27	KSRB 14.14-5 : Providing ceramic tiles of approved make, shade and size for flooring, treads of steps and landings laid on a bed of 12mm thick, cement mortar 1:3 mix, flush pointing with white cement using colour pigment, including cost of materials, labour, curing, complete as per specifications. ceramic tiles 400X400X20mm	Sqm	1191.0	168246.6	Rupees One Thousand One Hundred Ninety One Only
71	46.88	KSRB 14.14-5 : Providing ceramic tiles of approved make, shade and size for flooring, treads of steps and landings laid on a bed of 12mm thick, cement mortar 1:3 mix, flush pointing with white cement using colour pigment, including cost of materials, labour, curing, complete as per specifications. ceramic tiles 15X15cms 6mm thick	Sqm	935.0	43828.1	Rupees Nine Hundred Thirty Five Only
72	50.00	Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement and testing of joints complete. (internal work exposed on wall) - 25mm nominal OD pipes. 20mm dia CPVC pipe .	Mtr	126.0	6300.0	Rupees One Hundred Twenty Six Only
73	30.00	25mm dia CPVC pipe	Mtr	167.0	5010.0	Rupees One Hundred Sixty Seven Only
74	29.00	32mm dia CPVC pipe	Mtr	217.0	6293.0	Rupees Two Hundred Seventeen Only
75	7.00	Providing white vitreous china clay indian pattern squatting urinals with white glazed foot rests of approved quality and make conforming to ISI specifications and fixing in position with M-15 as directed of size 50.8 cms X 38 cms X 10.16 CMS - A grade(Rate includes cost of all materials, and conveyance to work spot).	Each	981.0	6867.0	Rupees Nine Hundred Eighty One Only
76	9.00	Providing and fixing CI Nahani trap of approved make conforming to ISI specifications and construction of Cistern in M-15 as per directions (Rate is inclusive of cost of materials and fixtures and conveyance of materials to work spot).	Nos	288.0	2592.0	Rupees Two Hundred Eighty Eight Only

Signature of the Contractor

Executive Engineer

Scanned by CamScanner

Sl No	Modified Quantity	Description	Unit	Approved Tender Rates of GOPIREDDY ( )		
				In Figures		In Words
77	23.00	KSRB13-6.1-1 : Providing and fixing in position brass bib cock of approved quality 15mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification No.KBS 13.2.2 / 13.3	Nos	233.0	5359.0	Rupees Two Hundred Thirty Three Only
78	6.00	KSRB 12-8.1 : Constructing brick masonry inspection chamber 455x610mm, and 450mm depth, (clear inside dimension) for single pipeline, using table moulded non-modular bricks of class designation 50 in cement mortar 1:5, C.I cover withframe (light duty) 455x610mm internal dimensions, total weight of cover with frame to be not less than 38 kg (weight of cover 23kg and weight of frame 15 kg) R.C.C. top slab with cement concrete M 15 with 20mm and downsize granite metal, foundation concrete M 5 with 40mm and downsize granite metal inside plastering 12mm thick with cement mortar 1:3, finish smooth with a floating coat of cement on walls and bed concrete complete as per standard design including cost of materials, labour charges, curing complete as per specifications.	Nos	7120.0	42720.0	Rupees Seven Thousand One Hundred Twenty Only
79	9.00	KSRB 11-5 : Providing and fixing white vitreous china clay, water closet European type (Pedestal type, P-trap) with black solid plastic seat and lid, C.P brass hinges, rubber buffers. 10 litre low level, P.V.C flushing cistern (all are approved make) with fittings, C.I/M.S brackets, 40mm diameter flush bend with fittings and clamps, overflow arrangements with special and 25mm mosquito proof coupling of approved design, painting of fittings and brackets, including cost of materials, labour complete as per specification.	Nos	5188.0	46692.0	Rupees Five Thousand One Hundred Eighty Eight Only
80	5.00	KSRB 11-11.1 : Providing and fixing white vitreous china clay, flat back wash basin size 630x450mm with a pair of 15mm C.P brass pillar taps with C.I / M.S brackets, 32 mm C.P. brass waste of standard pattern, painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications. Specification No. KBS 11	Nos	3930.0	19650.0	Rupees Three Thousand Nine Hundred Thirty Only
81	2.00	KSRB 13-11.1 : Providing and placing on terrace, polyethylene water storage tanks as per IS 12701 : 1996 with manhole lid and suitable locking arrangements, making holes of suitable diameter for inlet, outlet and over flow pipes, including cost of all materials, labour, transport charges, HOM of equipments and testing complete as per specifications. (For 1000 litre capacity)	Nos	8563.0	17126.0	Rupees Eight Thousand Five Hundred Sixty Three Only
82	115.20	Providing and finishing external walls in two coats over one coat of 100% acrylic silicon glazed primer with antifungal paint for top coat of approved brand and shade to give an even shade after thoroughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per	Sqm	152.0	17510.4	Rupees One Hundred Fifty Two Only

Gopireddy
Signature of the Contractor

Executive Engineer

Scanned by CamScanner

Sl No	Modified Quantity	Description	Unit	Approved Tender Rates of GOPIREDDY ( )		
				In Figures		In Words
83	49.00	Providing and installing at site of work 63mm (0.662) PVC Pipes of 6 kg / cm2 including cost of pipes and specials and labour, including lowering into trenches, laying true to line, level and perfect linking at joints leak proof including jointing of approved type with all labour and lift charges, handling charges including encasing the pipe alround to a depth not less than 15cms with gravel or selected earth available from the excavation etc., complete (P.NO - 94, I.NO - 13.73.2, PWD SR 16-17)	Nos	345.0	16905.0	Rupees Three Hundred Forty Five Only
84	22.05	Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m and lift upto 1.5m including cost of all labour complete as per specifications (P.NO - 6, I.NO - 2.11, PWD SR 16-17)	Sqm	75.0	1653.8	Rupees Seventy Five Only
85	0.00	KSRB 4-1.2 : Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2.	Cum	5103.0	0.0	Rupees Five Thousand One Hundred Three Only
86	0.00	KSRB 5.2-3 : Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13	Cum	5061.0	0.0	Rupees Five Thousand Sixty One Only
87	0.00	KSRB 5.2-1 Providing and constructing granite / trap / basalt rubble stone masonry in foundation with mud mortar, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.12 Page No. 22/ Item No. 5.4/ PWD SR 2016-17	Cum	5061.0	0.0	Rupees Five Thousand Sixty One Only
88	0.00	KSRB 4-1.6 ; Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregtes @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, ncluding cost of all materials, labour, HOM of machinery, curing complete as per specifications Specification No. KBS 4.1, 4.2.	Cum	6079.0	0.0	Rupees Six Thousand Seventy Nine Only
89	109.16	KSRB 5-14 : Providing and constructing load bearing wall with solid concrete blocks of size 400x200x200 mm having block density not lessthan 1800 kg/m3 and having a minimum average compressive strength 5.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing complete as per specifications. KBS No.5.4(Quantity upto 125%)	Sqm	947.0	103376.9	Rupees Nine Hundred Forty Seven Only

Signature of the Contractor

Executive Engineer

Scanned by CamScanner

Sl No	Modified Quantity	Description	Unit	Approved Tender Rates of GOPIREDDY ( ) In Figures		In Words
	77.59	(Quantity above 125%)	Sqm	922.3	71564.8	Rupees Nine Hundred Twenty Two and Thirty One
90	0.00	KSRB 6-2.3 Providing and constructing burnt brick masonry with approved quality of non-modular bricks of standard size of class designation 50 (table moulded) with cement mortar 1:6 for basement and superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. Specification No. KBS 6.2, Page No. 27/ Item No. 6.6/ PWD SR 2016-17	Sqm	6760.0	0.0	Rupees Six Thousand Seven Hundred Sixty Only
91	0.00	KSRB 4-6.3: Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness above 200 mm including cost of all materials, labour complete as per specificaiton. Specification No. KBS 4.6.2 P.NO.15.I.NO.4.30	Sqm	388.0	0.0	Rupees Three Hundred Eighty Eight Only
92	0.00	KSRRB M 2300-2.1 : Plain/reinforcement Cement Concrete design mix M20 super structure with OPC cement @320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @0.46cum with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-1508 height upto 5 mtrs	cum	6800.0	0.0	Rupees Six Thousand Eight Hundred Only
93	0.00	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and I or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per	Mton	56684.0	0.0	Rupees Fifty Six Thousand Six Hundred Eighty Four Only
94	0.00	KSRB 9-7.1 : Providing and fixing in position fully pannelled mathi/Nandi wood shutters for doors, styles and rails of 30mm. Thick with bottom and lock rails 180mm wide top rail and styles 100mm wide as per drawing and panels of 25mm thick including cost of materials, labour, HOM of machineries complete as per specifications. (excluding cost of fixtures) specification NO. KBS 9.34	Sqm	2670.0	0.0	Rupees Two Thousand Six Hundred Seventy Only
95	3.15	PVC DOOR Shutter : Supply and fixing of doors shuttersmade of rigid PVC extruded hollow section of 20mm X 200mm with the wall thickness of 1.0mm + /0.1mm equally divided into 4nos with tongue and groove locking arrangements. The shutter frame is made of 58*24 mm with the wall thickness of 1.5mm+/-0.15mm section metricut and joined at 4 corners with 125mmX225mm plastic brackets. The shitter shall be horizontally reinforced with 2nos of 8mm PVC rods. Teak wood battons shall be reinforced inside the door shutter during the fabrication of the door shutter at those points wherever the hardware is fixed on to the door shutter	Sqm	1780.0	5607.0	Rupees One Thousand Seven Hundred Eighty Only

Signature of the Contractor

Executive Engineer

Scanned by CamScanner

S No	Modified Quantity	Description	Unit	Approved Tender Rates of GOPIREDDY ( )		
				In Figures		In Words
96	0.00	KSRB15-3.10 : Providing 20mm thick cement plaster in single coat with cement mortar 1:3, to stone masonry & concrete surface including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.	cum	262.0	0.0	Rupees Two Hundred Sixty Two Only
97	0.00	KSRRB M100-1 Loading and Unloading of Stone Boulder / Stone aggregates /Sand/ Kanker / Moorum. KSRRB M100-1 : Placing tipper at loading point, loading with front end loader,dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications. MORTH -100 Chapter 1 Disposing of the excavated materials to a distance of 15.00kms by mechanical means	Cum	108.0	0.0	Rupees One Hundred Eight Only
98	0.00	Removing B.S Slab of Drain and stacking Page No. 25/ Item No. 5.32/ PWD SR 2016-17	Sqm	62.0	0.0	Rupees Sixty Two Only
99	0.00	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar(1:6) including fixing curing etc, complete -do- 7.5 cms thick Page No. 28/ Item No. 5.31.1/ PWD SR 2016-17	Sqm	635.0	0.0	Rupees Six Hundred Thirty Five Only
100	0.00	KSRB 4-1.7 : : Providing and laying in position plain cement concrete of mix 1:3:6 withOPC cement @ 220kgs, with 20mm and down size graded granite metal coarse aggregates @0.84cum and fine aggregates @0.56cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2/P No. 13/ Item No. 4.7/ PWD SR 2015-16	Cum	5142.0	0.0	Rupees Five Thousand One Hundred Forty Two Only
101	0.00	KSRB 5-14 : Providing and constructing precast concrete solid blocks with compressive strength not les than 35 Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x20x20 cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. Page No. 24/ Item No. 5.27/ PWD SR 2016-17	Sqm	930.0	0.0	Rupees Nine Hundred Thirty Only
102	0.00	KSRB 4.2.2 : Providing and laying in position plain cement concrete of mix M20 withOPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum with superplastesisre @ 3lts conforming to IS9103-1999Reffirmed machine mixed exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, walls(any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour HOM of machinery, curing, complete as per specifications. Specification. No. KBS 4.1,4.6, No. KBS 4.1,4.6, No. 13/ Item No. 4.11/ PWD SR 2016-17	Cum	5966.0	0.0	Rupees Five Thousand Nine Hundred Sixty Six Only

Executive Engineer

Gopireddy
Signature of the Contractor

Scanned by CamScanner

Sl No	Modified Quantity	Description	Unit	Approved Tender Rates of GOPIREDDY ( ) In Figures		In Words
103	0.00	KSRB 15-17.6: Providing and applying painting two coats (excluding priming coat) on new wood surface and / or wood based surface with enamel paint to give an even shade, cleaning the surface of all dirt, dust and foreign matter, sand papering including cost of materials, labour, complete as per specifications. Page No.125 / Item No. 15.60 / PWD SR 2016-17	Sqm	85.0	0.0	Rupees Eighty Five Only
104	0.00	Providing and fixing M.S Gate as per Cheaf Architect Drawing using 50mmX50mm 14 guage M.S hollow pipe frame work bent to ornamental shape as shape as shown in the drawing and 35mmX6mm and 16X16mm squre roads for verticals alternatively spaced at 4cms c/c in two halves and 40mmX6mm M.S flats for horizontal member and at at the top cast iron spikes are provided at alternate vertical members as shown in the drawing etc., complete. All the steel surface should be thoroughly cleaned free of of rust and painted with anti corrosive paint (shop paint) etc., complete the work includes cost of all materials, labour charges for all item of work, hire charges of welding, cutting and grainding equipment, and electricity charges, with lead and lift loading and lunloading charges. etc., complete as per specification and drawing Page No.47/ I No. 7.37/ PWD SR 2016-17	Sqm	2967.0	0.0	Rupees Two Thousand Nine Hundred Sixty Seven Only
105	0.00	Refixing stone slabs of drains and pointing in C.M (1:3) Page No. 25/ Item No. 5.33/ PWD SR 2016-17	Sqm	77.0	0.0	Rupees Seventy Seven Only
106	0.00	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC)for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, form works and scaffoldings to withstand pumping of concrete, with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Ready mixed Cement concrete M-20 for raft foundation, column footing, main and secondary beams. Page No. 18/ Item No. 4.48/ PWD SR 2016-17	Cum	5835.0	0.0	Rupees Five Thousand Eight Hundred Thirty Five Only
107	13.62	KSRB 2.3 : Filling available excavated earth (excluding rock) in sides of foundations upto plinth in layers not exceeding 20cms, in depth, compacting each deposited layers by ramming after watering with lead upto 50m, and lift upto 1.5m, including cost of all labour complete as per specifications, specification. (P.NO - 6, I.NO - 2.11, PWD SR 16-17)	Cum	128.0	1742.8	Rupees One Hundred Twenty Eight Only
108	0.00	KSRB 4.9.2:providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications.Specification No. KBS 4.6.3 Page No. 17/ Item No. 4.46.2/ PWD SR 2016-17	Qntl	60157.0	0.0	Rupees Sixty Thousand One Hundred Fifty Seven Only

Signature of the Contractor

Executive Engineer

Scanned by CamScanner

Item No	Modified Quantity	Description	Unit	Approved Tender Rates of GOPIREDDY ( )		
				In Figures		In Words
109	0.00	KSRB 11-11.1 : Providing and fixing white vitreous china clay, flat back wash basin size 630x450mm with a pair of 15mm C.P brass pillar taps with C.I / M.S brackets, 32 mm C.P. brass waste of standard pattern, painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications. Specification No. KBS 11 [P.No.80-1.No.12.23]	Nos	3930.0	0.0	Rupees Three Thousand Nine Hundred Thirty Only
110	0.00	KSRB 8.6-5: Providing and fixing in wall surface 2.5 kg/sq.cm H.D.P.E. rain down water pipes 90 mm outer dia approved make and brand with necessary specials like shoes bends and offsets fixed with iron clamps, walls plugs, screws, including cost of materials, labour,Curing complete as per specifications. Page No. 52/ Item No. 8.16/ PWD SR 2016-17	M	402.0	0.0	Rupees Four Hundred Two Only
111	6.75	KSRRB M200-15.2. Dismantling of existing structures like culverts,bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specifications. iii) Dismantling Stone Masonry.B. Rubble stone masonry in cement mortar MORTH Specification No. 202 Page No: 137 Item No:18.27	Cum	247.0	1667.3	Rupees Two Hundred Forty Seven Only
112	1692.80	Excavation and removal of silt and silt mixed with sand in slussy condition from canal bed including disposing off the same in spoil bank or on the canal embankment in layers as directed etc., complete with lead upto 50 m and all lifts. (16-17,P.157,I.WRD:8.35)Quantity upto 125%	Cum	471.0	797308.8	Rupees Four Hundred Seventy One Only
113	0.00	KSRRB M2100-5.1. Earth work in excavation for foundation of structures as per drawing and technical specifications, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material complete as per specifications. "V. Marshy soil - A. Manual Means Upto 3 m depth MORTH Specification No. 304 Page No: 216 Item No:27.12	Cum	502.0	0.0	Rupees Five Hundred Two Only
114	0.00	KSRRB M2100-13 - Plain Cement Concrete M15 with OPC cement @ 240 kgs, with 40mm and down size graded granite metal coarse aggregates @0.84 cum and fine aggregates @ 0.56cum, in open foundation complete as per Drawing and Technical Specification MORTH Specification No.1500, 1700 & 2100	Cum	5937.0	0.0	Rupees Five Thousand Nine Hundred Thirty Seven Only
115	0.00	KSRRB M 2100-17.2 : Plain/reinforcement Cement Concrete design mix M25 with OPC cement @340 kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.70cum and fine aggregates @0.47cum with superplastisiser @ 3lts confirming to IS9103-1999 Reaffirmed-2008, open foundation complete as per Drawing and Technical Specification with Batching plant, transit mixer and concrete pump. MORTH Specification No. 1500, 1700 & 2100	Cum	6153.0	0.0	Rupees Six Thousand One Hundred Fifty Three Only

Executive Engineer

Signature of the Contractor

Scanned by CamScanner

No	Modified Quantity	Description	Unit	Approved Tender Rates of GOPIREDDY ( ) In Figures		In Words
116	4.02	Stone masonry work in cement mortar 1:3 for substructure complete as per drawing and technical specification B. Ramdom Rubble Masonry (Coursed uncoursed) MORTH specifications No.1405.4 with available stones	Cum	3089.0	12417.8	Rupees Three Thousand Eighty Nine Only
117	2.70	Stone masonry work in cement mortar 1:3 for substructure complete as per drawing and technical specification B. Ramdom Rubble Masonry (Coursed uncoursed) MORTH specifications No.1405.4 with New stones	Cum	4024.0	10864.8	Rupees Four Thousand Twenty Four Only
118	39.12	Providing Rulled pointing to course stone masonry with cement mortar 1:3, 20mm deep, after raking joints o depth of 20mm nicely lining , including cost of materials, labours, curing complete asper specification.	Sqm	99.0	3872.9	Rupees Ninety Nine Only
E1	28.77	KSRB 4-6.1 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for foundations, footings, bases of columns for mass concrete including cost of all materials, labour complete as per specificaitons	Sqm	260.9	7506.6	Rupees Two Hundred Sixty and Ninety One Paise Only
E2	44.82	Cement concrete pavement.Construction of un-reinforced plain cement concrete pavement, using a grade concrete M30 over a prepared base with OPC coarse aggregate @ 0.69cum fine aggregate @ 0.46cum,coarse and fine aggregate confirming to IS:383-2016,with superplastisiser @3lts confirming to IS9103-2008mixed in a concrete mixer of not less than 0.6 cum capacity and appropriate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the form work as per drawing). Spreading the concrete with shovels, rackers compacted using needle, screed and plate vibrator and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints including groove cutting charges, joint filler, separation membrane, selant primer, joint sealant, admixtures as approved, curing compound, finishing to lines and grades, textured with texturing machine.and curing including cost of all materials,labour,hire chargedof machines,all lead and lift charges etc., complete as per specifications. - do with OPC at 360Kg per cum coarse aggregate @ 0.69cum and fine aggregate @ 0.46cum Pg No.177 Item No.22.6.1	Cum	5375.5	240930.2	Rupees Five Thousand Three Hundred Seventy Five and Fifty Paise Only
E3	2549.19	Fabricating, supplying and erecting M.S. Tubular Truss of all spans as per approved drawing and design with prefabricated steel application using quality material and are durable, reliable and corrosion and abrasion resistant.Welding shall confirm to latest structural welding code. Quality shall be on various parameters like shape, size, design guage and polish. The entire truss is anchored in RCC column by using 4 Nos. of M.S. anchor bolts at each support, with 10mm thick base plate and shoe plate.The work includes cutting, straightening, placing in position of M.S pipes and wleding wherever necessary, and applying one coat of red oxide primer coat to all the members including cost of all materials, labour charges, and hire charges of machineries for cutting, welding, grinding and erection equipments, with all lead and lift, transportation, etc., complete as per specification. (Page No. 40 Item No. 7.29 of CSR 2016-17).	kgs	112.3	286160.9	Rupees One Hundred Twelve and Twenty Five Paise Only

Signature of the Contractor

Executive Engineer

Scanned by CamScanner

No	Modified Quantity	Description	Unit	Approved Tender Rates of GOPIREDDY ( )		
				In Figures		In Words
E4	78.20	PROVIDING TRAPEZOIDAL PROFILED SHEET Providing and installing of pre painted Galvolume iron Trapezoidal profiled sheet of approved make 1060 mm width (1000 mm cover width), 28-30 mm crest height with crest distance of 200 mm c/c with 2 ribs at the centre for stiffening. The total coated thickness (TCT) of the sheet will be 0.47 mm +/- 0.02 mm tolerance Zinc-Alu Alloy coating AZ150 gsm as per ASTM 1397/A755-550 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 20-22 microns using self drilling/self tapping screws of 25 mm length, to be fixed over the existing purlins, rafters, channels and trusses	Sqm	695.8	54407.4	Rupees Six Hundred Ninety Five and Seventy Eight Paise Only
E5	4.88	Waterproofing of RCC Terrace / podium slab / toilet / utilities / water retaining structure by preparing the surface by chipping and cleaning and Grouting of Honey comb, voids,cracks / construction joints with cement slurry (1kg cement added in 10 ltr of water) added with 100gm of inorganic accelerator, followed by spraying of liquid biological modified alkaline earth silicates @ 0.40 ltr per sqm on whole surface to reduce the micro porosity and allowing it to dry, curing the surface for the silicates to penetrate deeper into the concrete and spraying waterproofing impregnate liquid containing silane and silanol linear copolymer @ 0.50 ltr per sqm and finally applying polymer slurry made out of cross linked acrylic / styrene / butadiene & cement in the ratio of 1:0.1, @0.50kg/sqm on the whole surface, including all labour charges tools and equipments, all complete as per the specification. page no 69 item no 10.5.1	Sqm	532.0	2593.3	Rupees Five Hundred Thirty One and Ninety Five Paise Only
E6	8.51	KSRB15-5.2 : Providing rough cement plastering 15mm thick in single coat with cement mortar 1:6, to brick masonry for base of dadooing works with sand of approved quality, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.	Sqm	194.2	1651.4	Rupees One Hundred Ninety Four and Seventeen Paise Only
E7	12.36	KSRB 2.8 : Providing and Filling in foundation with granite / trap broken metal 100mm. and down size, with approved sand including hand packing, ramming, watering, including cost of all materials and labour with all lead and lift. complete as per specifications. Specification No. KBS Pg No 7, Item No 2.15	Cum	2456.5	30354.7	Rupees Two Thousand Four Hundred Fifty Six and Forty Seven Paise Only

Signature of the Contractor

Executive Engineer

Scanned by CamScanner